

Bureau of Mines Report of Investigations/1972

Methane Emission Rate Study in a Deep Pocahontas No. 3 Coalbed Mine in Conjunction With Drilling Degasification Holes in the Coalbed



Report of Investigations 7703

Methane Emission Rate Study in a Deep Pocahontas No. 3 Coalbed Mine in Conjunction With Drilling Degasification Holes in the Coalbed

By Stephen Krickovic and J. D. Kalasky
Pittsburgh Mining and Safety Research Center, Pittsburgh, Pa.



UNITED STATES DEPARTMENT OF THE INTERIOR Rogers C. B. Morton, Secretary

BUREAU OF MINES Elburt F. Osborn, Director

CONTENTS

		<u>Page</u>
Abs	stract	1
Int	troduction	ī
Acl	knowledgments	2
Des	scription of study area	2
Mit	ning method and equipment	3
Ver	ntilation	3
Mor	nitoring	3
Dri	illing horizontal methane control holes into coalbed	6
Res	sults	8
	nclusions	
	ILLUSTRATIONS	
1. 2.	Location of study area	2
۷٠	Arrangement of ventilation, haulage, and locations of recording instruments	4
3.	Sequence of mining by shifts and dates during study period	4 5
٥. 4.	Locations of in-situ pressure and degasification boreholes drilled	ر
٠.	in coalbed	7
5.	Summary of pertinent results obtained from degasification holes	,
J.	in coalbed	10
	TABLES	
1.	Summary of drilling data	6
2.	In-situ gas pressure measured in hole 1	
3.	Summary of all monitoring data	

METHANE EMISSION RATE STUDY IN A DEEP POCAHONTAS NO. 3 COALBED MINE IN CONJUNCTION WITH DRILLING DEGASIFICATION HOLES IN THE COALBED

Ьу

Stephen Krickovic ¹ and J. D. Kalasky ²

ABSTRACT

A degasification experiment was conducted in a Pocahontas No. 3 coalbed mine in Virginia. It involved (1) drilling holes in the coalbed in the outside headings of a set of five being developed in virgin area, and (2) conducting a methane emission rate study as mining progressed and additional holes were drilled.

Degasification from all drill holes except the longest in each of the outside headings and the first three drilled (excluding the in-situ pressure hole), was erratic and inconsequential in methane emission rates. The two longest holes liberated 66 and 79 cfm of methane, which is significant for the coalbed, but such quantity lasted a relatively short time; the first three were uniform but low in methane emission.

INTRODUCTION

Methane is contained under pressure within the micropores, joints, and fracture systems in gassy coalbeds. Breaking coal from solid faces produces considerable coal surface areas that when added to the newly exposed solid coal surfaces increases methane emission rates appreciably.

The 1969 Federal Coal Mine Health and Safety Act requires that a minimum of 9,000 cfm of air be conducted to the last open breakthrough in any pair or set of developing headings. An additional requirement is that the minimum quantity of air in any coal mine reaching each working face shall be 3,000 cfm unless a greater quantity is needed to dilute the methane concentration, as required by the 1969 act. The dimensions and configurations of most continuous-mining equipment presently used at the face make it difficult to comply with the act generally and, in very gassy mines, practically impossible.

¹ Supervisory mining engineer.

³Mining engineer (now employed by the Island Creek Coal Co.).

³Cervik, Joseph. An Investigation of the Behavior and Control of Methane Gas. Min. Cong. J., v. 53, No. 7, July 1967, pp. 52-57.

The objective of this study was to determine the effect on methane emission rates from the immediate face areas of holes drilled in the coalbed as mining progressed.

ACKNOWLEDGMENTS

The cooperation of the mine management of the Island Creek Coal Co. of Cleveland, Ohio, and Keen Mountain, Va., and of J. D. Hadden, mining engineer, Pittsburgh Mining Research Center, and his drilling crews is greatly appreciated.

DESCRIPTION OF STUDY AREA

The study area consisted of a set of five headings and breakthroughs being developed in virgin coal. Figure 1 shows the area and its relationship to the nearest mine workings and to projected mine plans on either side.




FIGURE 1. - Location of Study Area.

MINING METHOD AND EQUIPMENT

A two-step, ripper-type continuous miner was used in development of the set of five headings on 80- and 95-ft centers, with breakthroughs on 94-ft centers. Width of places averaged 17 ft, and thickness of coalbed mined, 53 in. The miner was equipped with a methane detector located 10 ft ahead of the operator. When the detector indicated a methane concentration of 2 pct, the power was automatically disconnected.

Owing to the very gassy condition of the coalbed, the miner was advanced usually only 4 ft in each lift (one-half the width of the working face) after which it had to be maneuvered to the other half of the place. This procedure would involve 10 maneuvers for the full 20-ft-deep cut, at the end of which the operator was under the last line of roof support. The miner then was trammed to the next face in the cycle where the aforementioned mining procedure was repeated, and bolting of roof was undertaken in the preceding place.

Coal was discharged by the miner directly into 5-ton-capacity cable reel shuttle cars that traveled to the feeder at the tailpiece of the 36-in belt conveyor for unloading. Two shuttle cars serviced the miner.

VENTILATION

Figure 2 shows the arrangements of ventilation, haulage, and locations of recording instruments with respect to working faces at the start of study.

Headings 2-4 served as intakes. Next to the last complete line of breakthroughs, the air was divided by plastic stoppings and line brattice into two splits, one ventilating only heading 5, and the other ventilating the remaining headings. When headings 3 and 4 were mined, the areas ventilated were more evenly divided. In all cases, air was conducted to the working face by line brattice erected to facilitate movement of intake air over the men and equipment and to prevent obstruction of travel to mine equipment.

MONITORING

Recording anemometers and methanometers were installed at stations A and B in headings 1 and 5, respectively, and recording methanometers, only at stations C and D in headings 1 and 5, respectively (fig. 2).

Locations for instrumentation were selected to obtain reasonably uniform air velocities in the cross-sectional areas. At stations A and B, a grid system of horizontal and vertical strings that formed 1-ft squares was set up in the cross-sectional areas. Air velocities were measured in each square with the sensing head of a recording anemometer, and the square in which the air velocity most closely approached the average for the cross-sectional area was selected. The sensing heads of the continuously recording methanometers and anemometers⁴ were installed in the velocity square with value closest to

⁴La Scola, J. C., and Joseph Cervik. Development of Recording Methanometers and Recording Anemometers for Use in Underground Coal Mines. BuMines Tech. Prog. Rept. 15, May 1969, pp. 9-14.




FIGURE 2. - Arrangement of Ventilation, Haulage, and Locations of Recording Instruments.

the average. Area at station A in heading 1 was 73.9 sq ft, and average velocity was 347 fpm. The area with 350-fpm velocity was used. The corresponding values at station B in heading 5 were 72.0 sq ft, 285 fpm, and 290 fpm (fig. 2). At stations C and D, the sensors of the methanometers were located at the point of average methane concentrations in the cross-sectional areas as determined by three hand-held methanometer readings at each location.

The air volumes measured at stations A and B were used also for stations C and D, since air leakage through stoppings between the two sets of stations was negligible.

A monitoring team consisted of the following: A mining engineer, who time-studied the miner, observed unusual conditions at the face affecting methane emissions, measured the methane content in the intake air 5 ft inby the belt conveyor tailpiece, and secured other pertinent data; and two technicians who maintained the instruments in satisfactory operating condition by adjusting them, by replacing weak or dead batteries and malfunctioning instruments with spare units, and by making check readings periodically with handheld instruments.

Although the mine worked two shifts per day, monitoring was conducted mostly on the first shift (8 a.m. to 4 p.m.). Owing to transportation problems, the monitoring crew could not start the instruments until 10 or 11 a.m., and all instruments could not be started simultaneously. The monitoring time,




FIGURE 3. - Sequence of Mining by Shifts and Dates During Study Period.

therefore, was based on the recording methanometer having the shortest operating period, and the data recorded on the other three units for the corresponding periods were used.

The areas mined and the sequence of mining are shown in figure 3.

DRILLING HORIZONTAL METHANE CONTROL HOLES INTO COALBED

A 56-1b Thor⁵ hand-held air drill equipped with EW, 1-13/16-in-diam smooth-walled drill casing 2-31/32-in-OD centralizers, and a 3-in Blue Demon three-pronged insert bit were used. A 1-ton hand-operated hoist provided the thrust for the drill, and water was used as the flushing agent.

Eight holes were drilled in the coalbed (fig. 4 and table 1); hole 1 (in-situ gas pressure) was packed with nine packers spaced with 5-ft lengths of 3/4-in pipe. Fifteen ft of the hole was left open at the front end, and 10 ft, at the back end.

Hole		Depth of hole, ft	Hole started	Angle of hole in coalbed	Hole termi- nated in
1	1970 06-27	108	Inby rib of breakthrough between headings 2 and 3.	Parallel to headings.	Coal.
2	06-28	255	12 in below binder left rib of heading 1.	4° angle with respect to rib in heading 1.	Do.
3	06-29	259	24 in below binder left rib of heading 5.	5° angle with respect to rib in heading 5.	Do.
4	07-01	95	12 in right of hole 3 in heading 5.	10° angle with respect to rib in heading 5.	Roof rock.
5	07-19	503	12 ft back from face of heading 1.	10° angle with respect to rib in heading 1.	Coal.
6	07-23	140	Near hole 3 in heading 5.	Unrecorded angle with respect to outside rib in heading 5.	Roof rock.
7	07-25	90	Near hole 3 in heading 5.	Unrecorded angle with respect to outside rib in heading 5.	Bottom rock
8	07-26	300	190 ft from hole 3 and 30 ft outby face in head- ing 5.	10° angle with respect to rib in heading 5.	Coal.

TABLE 1. - Summary of drilling data

⁵Reference to specific brands is made for identification only and does not imply endorsement by the Bureau of Mines.




FIGURE 4. - Locations of In-Situ Pressure and Degasification Boreholes Drilled in Coalbed.

A 1-1/2-in-diam plastic pipe was grouted a distance of 8 to 10 ft in holes 2-5. The pipe was extended just outby the recording methanometers at stations C and D in headings 1 and 5, respectively, except that pipe from hole 4 was tapped into pipe from hole 3. A 50-ft-long EW rod was inserted in hole 5 prior to the grouting of the plastic pipe. Drill casing was placed in hole 8, and the plastic pipe was attached to it and extended outby the recording methanometers as were the others. Holes 6 and 7 were left open, because neither liberated any measurable quantity of methane.

RESULTS

The lowest pressure in table 2 is not representative for the total study period, because the usefulness of the hole was negated July 14 (fig. 3-4), after which holes 5-8 were drilled.

TABLE 2. - <u>In-situ gas pressure</u> measured in hole 1

Date, July	Gas pressure, psi
1	649
2	650
8	645
9	642
10	640
13	636

Approximate overburden at hole 1 was 1,450 ft.

Table 3 is a summary of all monitoring data obtained during the study period, and figure 5 shows the effect of the holes drilled in the coalbed on methane emissions from the face areas.

As holes 2-4 were completed, there was some uniformity in methane emissions from them, reaching a maximum of 42 cfm (60,500 cfd) upon completion of hole 4. It is doubtful that hole 1 (in-situ pressure) contributed a measurable quantity of methane.

From July 1 until hole 5 was completed on July 19, and during which period mining in the study area continued for 6 consecutive days, the emission rates from the holes were erratic and, with three exceptions, practically nil. Unknown conditions in the holes, possible errors in instrumentation, relatively short monitoring periods for 8 days, and personal errors could be the explanation for the erratic values.

ieft spli	ieft spli	ieft spli	ieft spli	Left spli	Left spli	Left spli	Left spli	t epli	فلست	44		Right	🔐					3	Methane	Methane emission in face	2 8	Methane entssion face	
Monitoring time, Face Coal Miner and pro- on Air,	Monitoring time, Face Coal Miner min ad- pro- on Air,	Monitoring time, Face Coal Miner	ring time, Face Coal Miner min ad- pro- on Air,	ad- pro- on Air,	pro- on Air,	on Air,	Air,			g i	g				-	Total	Methane		intake			hori-	
Idle Total ft tion, min tons	WOFFIRE tace work- Idle Total ff tion, min ing ing tons	work- Idle Total ff tion, min ing tons	Idle Total ft tion, min tons	ft tion, min tons	duc- spilt, cim tion, min tons	Bin cil	5		- B - CT - CT - CT - CT - CT - CT - CT - CT		n min	3			<u></u>	C and D Pet Cfm	B Pet Cfm	2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2	tail- piece	, -	C and D and stations		
3 Idle 480 480 25,200 - 0.55	480 480 25,200 -	- 480 480 25,200 -	480 25,200 -	25,200 -	- 25,200 -	25,200 -	25,200 -	•	Г	110		19,600		0.45	44,800	<u>-</u>	0.50	227	0.23 105	<u> </u>			All recording instruments installed at stations A and B, 06-21-70.
1 (4-5),5,(4-5) 136 269 405 42 131 64 25,000	136 269 405 42 131 64 25,000	136 269 405 42 131 64 25,000	269 405 42 131 64 25,000	42 131 64 25,000	131 64 25,000	64 25,000	25,000			ø			- 8	7 87	3,700	•		246	24 105				
06-23-70 1 5,4 91 204 295 31 97 28 24,700 -	91 204 295 31 97 28 24,700	91 204 295 31 97 28 24,700	204 295 31 97 28 24,700	31 97 28 24,700	97 28 24,700	97 28 24,700	24,700			5	5 63	17,900		6.	2,50		50.0	278	25 10				
1 1.(2-1).1 79 201 280 37 116 14 21.900	79 201 280 37 116 14 21.900	79 201 280 37 116 14 21.900	201 280 37 116 14 21.900	37 116 14 21.900	116 14 21,900	16 14 21,900	21,900							100	300		_	315	27 105	_	•		
1 1, (2-1), 2, 1 122 258 380 67 209 47 21,000	122 258 380 67 209 47 21,000	122 258 380 67 209 47 21,000	258 380 67 209 47 21,000	67 209 47 21,000	209 47 21,000	09 47 21,000	21,000			`:				.92	99,60	0.67		333		162	\$	1	Inby recording methanometers installed at stations C and D.
107 218 325 43 134 40 22,700	107 218 325 43 134 40 22,700	107 218 325 43 134 40 22,700	218 325 43 134 40 22,700	43 134 40 22,700	134 40 22,700	40 22,700	22,700	,700	. :	٠٠			8	۶۱	1,300		.73	90	25 105		' 3		i
3do	2480 480 - 24,800	2480 480 - 24,800	480 480 - 24,600 - 24,600	24,600	24,600	24,600	24,600	~	35				3 8	? ?	3 5	5.5		167			8 59	•	
1 do 480 480	480 480	480 480	480 480 - 26,800	26,800	26,800	26,800	26,800		32	3,3	9 47	17,600		22.	44,400	.47 207		122	2 2 2	102	333		Hole 1 (pressure) started.
	480 480 27,000	480 480 27,000	480 480 27,000	26,200	26,200	26,200	26,200		3 %	;			8 8 8 8	6.4	905	.48 211		273			2 29		
480 26,900	- 480 480 26,900	480 480 26,900	480 26,900	26,900	26,900				35			17,9		3	900	.38	95.	251	23 105		19	20	Hole 2 completed. Fan blade
1do 480 480 25,800 .35	480 480 25,800	480 480 25,800	480 25,800	25,800	25,800	25,800	25,800		35	. 52	- 2	21,800	00	85.	47,600	.38	. 55	262	.22 105	92	61	20	Hole 3 completed. Fan blade
1do 480 480 30,000 .33	480 480 30,000	480 480 30,000	480 30,000	30,000	30,000	30,000	30,000		33	87.	, eo	21,200	00 .42	.59	51,200	.37 189	. 53	271	.21 105	æ	61	21	coanges. Hole I completed. Fan blade
115	. 115 115	115 - 28,200	115 - 28,200	28,200	28,200				3,5	.56	9 0	18,9	74.	38.5	47,100	.39 184	.61	287	.22 10		19:	7,7	changes. Hole 4 completed.
1do 140 140 26,100	- 140 140 26,100	- 140 140 26,100	140 26,100	26,100	- 26,100	26,100	26,100		3 8	; 5		28,100		<u>.</u>	¥,78	2 % 3 %		<u>\$</u>		8	- 	7 7	
1do	480 480 26,500 .33	480 480 26,500 .33	480 - 26,500 .33	26,500 .33	26,500 .33	26,500 .33	26,500 .33	ដ		Š	8:2	28,1	88	£. 8	966	.33 18	44.	240	19 104		8 8 8	~ :	
1do 480 480 - 26,500	480 480 - 26,500	480 480 - 26,500	480 - 26,500	26,500	26,500	26,500	26,500		3 2	18		28,3		; 3	, 4 8 8 8 9	30 164		24.7			2 22	7 12	
395 395 26,300	395 395 26,300	395 395 26,300	395 395	10 26,300	26,300	26,300	26,300		31	2:	_			3:	500	.32 17		77.	190		% :	21'	
1 3,2,3,2 154 28 182 37 115 72	154 28 182 37 115 72 /25,700	154 28 182 37 115 72 /25,700	28 182 37 115 72 /25,700	37 115 72 /25,700	115 72 /25,700	72 /25,700	25,700		3 3				2.4.	. 9	9	.48 23	, 93 - 93	326			2 2	3 ′	
1 (3-2),1,(2-1),1 106 59 165 33 102 13 26,400	106 59 165 33 102 13 26,400	106 59 165 33 102 13 26,400	59 165 33 102 13 26,400	33 102 13 26,400	102 13 26,400	13 26,400	26,400		3	¥,	_			.75	1,900	.46 221	_	303			55	នះ	
108 251 39 121 78	143 108 251 39 121 78 24,000	143 108 251 39 121 78 24,000	108 251 39 121 78 24,000	39 121 78 24,000	121 78 24,000	78,000,42	2,42		3	27.				, y	45,500	52 23	5.6	328 296	2 2 2 2 2 2		8 %	2 2	
-	113 62 175 26 81 75 27,400 127 63 190 33 101 53 25,300	113 62 175 26 81 75 27,400 127 63 190 33 101 53 25,300	62 175 26 81 75 27,400 63 190 33 101 53 25,300	33 101 53 25,300	101 53 25,400	53 25,300	25,300		55	2. 29	2.38	22,100	8 8 52 52	. 62	48,900	. 54 264	79.	328	22 104	3,50	9 %	6 91	
008 72 75 081 59 087 782 96	75 081 29 787 90	75 081 29 787 90	384 480 65 180 54 26 800	65 180 54 800	180 54 200	24,800	96 800	-	. 4	۶				. 5	, ,			- 5			2	, 6	Hole 5 completed.
1 (3-4) (4-3) 83 397 480 61 177 48 24,500	83 397 480 61 177 48 24,500	83 397 480 61 177 48 24,500	397 480 61 177 48 24,500	61 177 48 24,500	177 48 24,500	48 24,500	24,500		3		58	21,300		96	45,800	.48 219		325	22 103	118	នេះ	នេះ	Hole 6 completed.
1 4,5,(4-5) 35 175 210 22 64 15 27,500	35 175 210 22 64 15 27,500	35 175 210 22 64 15 27,500	175 210 22 64 15 27,500	22 64 15 27,500	64 15 27,500	15 27,500	27,500		3 2					69.	45,800			356			22	8 %	Hole 7 completed.
73 305 378 48 139 40 26,000	73 305 378 48 139 40 26,000	73 305 378 48 139 40 26,000	305 378 48 139 40 26,000	48 139 40 26,000	139 40 26,000	40 26,000	26,000		9 9	5.5			8 8 2. 5	.65	45,900			326			2 2	# #	0
51 269 320 39 113 27 24,100	51 269 320 39 113 27 24,100	51 269 320 39 113 27 24,100	269 320 39 113 27 24,100	39 113 27 24,100	113 27 24.100	13 27 24,100	25,300		6.0	* E	81 24	2,300		4.8	20,900		_	363	21 102	ŝŝ	2 22	* 2	Hole 8 completed.
1 1,2,3, (3-2) 101 379 480 67 194 45 25,000 .59	101 379 480 67 194 45 25,000 .59	101 379 480 67 194 45 25,000 .59	379 480 67 194 45 25,000 .59	67 194 45 25,000 .59	194 45 25,000 .59	94 45 25,000 .59	25,000 .59	. 59	_	-			. 57	.75	47,300	. 58 273	3 .75	354	22 102		25	8	Tubing of hole 5 discon-
65 140 205 42 122 33 26,100 .42	65 140 205 42 122 33 26,100 .42	65 140 205 42 122 33 26,100 .42	140 205 42 122 53 26,100 .42	42 122 53 26,100 .42	122 53 26,100 .42	53 26,100 .42	26,100 .42	.42		-				.85	6.200	.55 25		356	22 102		51	25	nected at 1:15 p.m.
1 1,2,3 41 73 114 29 83 30 23,500 .71	41 73 114 29 83 30 23,500 .71	41 73 114 29 83 30 23,500 .71	73 114 29 83 30 23,500 .71	29 83 30 23,500 .71	83 30 23,500 .71	30 23,500 .71	23,500 .71	r.		.8	11	19,400	8.	.82	42,900	. 76 326	98.	378	. 24 102	224	22	-	Methane emission from all
														_					_				holes recorded by methanom-
1 2,3,(3-2) 47 153 200 35 100 30 21,900 .75	47 153 200 35 100 30 21,900 61 203 264 42 122 23 24 100	153 200 35 100 30 21,900	153 200 35 100 30 21,900	35 100 30 21,900	100 30 21,900	30 21,900	21,900		5.5	8;	17	19,000	2.7	8.6	40,900	.75 307	68.	364	25 102	502	2:	٠	Do.
158 355 73 228 79 26,600	197 158 355 73 228 79 26,600	158 355 73 228 79 26,600	158 355 73 228 79 26,600	73 228 79 26,600	228 79 26,600	79 26,600	26,600		v		_			8	9	72 35		36.5			4	٠ ;	Mothane nercenteese and air
																							velocities measured by
Numbers appearing by themselves represent faces of entries: hyphenated numbers	uring by themselves represent faces of entries; hyphenated number	ves represent faces of entries; hyphenated numb	esent faces of entries; hyphenated numb	ces of entries; hyphenated number	entries; hyphenated numbers appearing in parentheses refer to breakthroughs between entries	s; hyphenated numl	enated num	2	į	Appea	100	noren r	heses	- Lefer	o brea	1	- A						Managed Therroments.

Numbers appearing by themselves represent faces of entries; hyphenated numbers appearing in parentheses refer to breakthroughs between entries.

*Methane volume in intake air obtained by hand-held instruments just inby belt tailpiece during idle shift on July 26 and idle periods on several operating days, including August 20.

*Methane volume in intake air obtained by hand-held instruments on August 20; the values in *Methane blead-off from coal ribs between monitoring stations A, B and C, D was obtained by recording methanometers on shift 2, June 26, and by hand-held instruments on August 20; the values in between were prorated.

*Methane emissions from holes in coalbed obtained by subtracting from the total rate obtained at stations C and D and those from the coal ribs.

9




FIGURE 5. - Summary of Pertinent Results Obtained From Degasification Holes in Coalbed.

It is reasoned that on July 18, when face production was 81 tons and methane emission from the face areas was 160 cfm, emission from holes 2-4 was nil. After completion of the 503-ft-deep hole 5 on July 19, methane emission from the coal-producing faces dropped from 160 cfm on July 18 to 93 cfm on July 24, but methane emission from hole 5 increased from 22 to 58 cfm. Hole 6 (140 ft deep) was drilled during this period and showed no measurable methane emission. Although a significant reduction in face emission during July 19 to July 22 can be attributed to the 3 idle days, contribution from hole 5 also was significant due to 3 coal-producing days during the period (189, 177, and 125 tons during monitoring shift). It is not determinable why hole 5 required 2 full days to become more productive. However, there is the desirable correlation between production, lower methane emission from the face areas, and higher methane emission from hole 5. This was expected from the study.

Although the 24-cfm emission rate from hole 8 (300 ft deep) is low, drilling of the hole was completed on July 26 after monitoring was stopped. Thus, most of the 24 cfm can be assumed as being liberated from hole 5.

During the period from July 26 to July 29, holes 5 and 8, particularly the latter, generally had a positive effect on reducing the methane emission from the face areas during mining. Face emission dropped from 137 cfm on idle July 26 to 130 cfm on July 27 when production was 113 tons. Increase in the face emission rate to 171 on July 28 was 32 pct; the production increase was 72 pct. This could explain the apparent discrepancy. At the same time, tubing from hole 5 was disconnected prior to completing monitoring on the same date, which permitted both methanometers in the same heading to record the emissions from hole 5.

Thus, it appears that emission rates from holes 5 and 8, 59 cfm (85,000 cfd) and 79 cfm (113,800 cfd), respectively, were somewhat significant, considering the relatively low permeability of the coalbed.

Other results not related to methane emissions from the holes in the coalbed may be noted in table 3. They are as follows:

- 1. Methane concentrations in the left air split reached a high of 0.92 pct during the study. In the right air split the high was 1.03 pct; the next highest was 0.92 pct. However, the methane detector on the continuous miner disconnected the power at 2.0 pct concentration too frequently. This occurred despite the fact that the air volume measured at monitoring station A ranged from 20,800 to 30,000 cfm, and at station B, from 17,100 to 28,300 cfm.
- 2. The methane volume in the intake air measured inby the conveyor belt tailpiece was 105 cfm (151,200 cfd) at the start of the study and 102 cfm at the end of the study. This is a significant volume that accumulated from the bottoms of intake shafts, from the intake airways to the study area, and mostly from the 3,400 ft of three intake airways of the particular section. Coal in cars and on belt conveyors wherever located outby the study section also contributed to the volume of methane. All of these factors could account for the insignificant change in the intake air methane volume.
- 3. Methane emission from the ribs and parts of breakthroughs (to the stoppings) between monitoring stations A and C in heading 1 and monitoring stations B and D was 66 cfm (95,000 cfd) at the start of study and 44 cfm (63,000 cfd) at the end of study (58 days). The bleed-off is significant in a total distance equivalent to a single heading 2,000 ft long.

CONCLUSIONS

The behavior of methane emissions from the holes drilled in the coalbed, as described under "Results," strongly indicates the need for further research in the development of (1) the most effective spacing and length of holes; (2) proper angle of holes with respect to the outside ribs; (3) the possible use of strong slotted plastic pipe in the holes to prevent closure; and (4) other possible techniques to obtain greater and more lasting methane

emission rates. It is theorized that the somewhat sudden reduction in methane emissions from holes 5 and 8 was caused by closure.

Although not included in the objective of the study, development of techniques for more effective face ventilation and for degasification of gassy coalbeds or major panels before mining within them is needed. With respect to face ventilation, there is an urgent need in very gassy mines to develop airduct systems for mounting on predominantly used continuous miners. Also needed is telescoping tubing to be used back of the miners in conjunction with reinforced tubing and auxiliary fan. The arrangement would provide greater volume of air as close as practicable to the cutting head while the miner is breaking coal.

U.S. GOVERNMENT PRINTING OFFICE: 1972-709-184:543